

Fukushima & Three Mile Island Accidents & Spent Nuclear Fuel

January 31, 2012

Lake H. Barrett

Lake@Lbarrett.com

Disclaimer: Fukushima Information is preliminary especially regarding interpretation of events; opinions expressed are mine and mine alone.

Three Mile Island Units 1 & 2

March 28, 1979



Three Mile Island Unit-2 Accident


March 28, 1979



PORV

Relief Valve fails to close

Operators Believe Reactor Overfilled and Turn Off Injection Pumps






COLOR PLATE I. TMI 2

Adapted from 'SPECTRUM, A special report', November, 1979
Copyright © 1979 by the Institute of Electrical and Electronics Engineers, Inc.

Core is uncovered Fuel overheats/fails/~50% Melt


650,000 gallons of highly radioactive water collects

TMI Core Damage Sequence



TMI Core Configuration

~Evening 3/28/1979




Damaged Fuel Rods

Three Mile Island March 28, 1979

Hydrogen
Deflagration
28psig 13:00




~3M deep
water
1000R/hr



Recovery Cleanup Actions



Building Remediation to Gain Core Access (Barrett Entry)




Phased Unique Air and Water Cleanup Systems Created Based on Best Available Technology

TMI Damaged Core Removal

~1985-1990



TMI Defueling Sequence



Core Bore Machine



Defuel Can Loading



Can Transfers



Shipping Cask



Transport



Core Debris Storage

Three Mile Island History

- **Reactor Scram: 04:00 3/28/79**
- **Core melt and relocation: ~ 05:00 – 07:30 3/28/79**
- **Hydrogen Deflagration: 13:00 3/28/79**
- **Recirculation Cooling: Late 3/28/79**
- **Phased Water Processing: 1979-1993:Removed ~1.2MCi Cs137**
- **Containment Venting 43KCi Kr-85: July 1980**
- **Containment Entry: July 1980**
- **Reactor Head removed and core melt found: July 1984**
- **Start Defuel: October 1985**
- **Shipping Spent Fuel: 1988-1990**
- **Finish Defuel: Jan 1990**
- **Evaporate ~2.8M gallons Processed Water: 1991-93**
- **Cost: ~\$1 Billion**

Fukushima Daiichi Nuclear Power Station



Units 5 & 6


Dry SNF Storage

Units 1-4

Common
Spent Fuel
Pool


Tsunami Size: Main Safety Factor

3/11 15:45



GE Mark I Reactor Building


Boiling Water Reactor Design At Fukushima Daiichi



Browns Ferry Primary Containment



Battery Power Control of Steam-Driven Reactor Core Isolation Cooling System In Units 2 & 3 (Unit 1 Had Isolation Condenser which Operators Stopped)



Actions to Extend DC Power For Control




**Scavenged Truck Batteries To
Maintain Reactor Instrumentation**



**Control Room Operator
During Black Out**

Battery Power Exhausted




Core Uncovers and starts to overheat

Suppression pool (wet well) becomes saturated

3/12 ~02:00 JST

Venting Primary Containment



**Core
Overheated**

**Primary Containment Pressure~
~90psia @02:00 3/12**

**Uncertain Command & Control
Actions & Unit 1 Vent Valve**


Operability

3/12 ~05:30 U1

3/13 ~ 00:00 U2

3/13 ~ 08:40 U3

Hydrogen Leakage Paths



Unit 1 Reactor Building Explosion

3/12 15:31



Unit 3 Reactor Building Explosion

3/14 11:15




Unit 1 Reactor Building



Unit 3 Reactor Building

Before



Reuters

After



TEPCO


Fukushima: Reactor Vessel-Primary-Secondary Containment Sequence

Primary Coolant System



- Core Over Heats
- Clad Burst ~900C
- Clad Oxidize ~1200C
- H2 Release
- Partial Melt~1800C-2700C
- Primary Coolant System Overpressure

Primary Containment



- Vent from Primary Coolant Sys to Primary Containment- H2, Steam, & Fission Products (Xe, Kr, I, Cs etc)


L. Barrett Consulting LLC

Secondary Containment



- No Primary Containment Cooling therefore Primary Containment Overpressure- Vent to Secondary Containment

Cores Melted, Slumped Into Lower Head & Likely Failed Some CRD Penetrations



Original Core

Melted Core dropped

RPV Thermal Failures


Core on Floor

Degree of fuel damage

-  : Normal fuel
-  : Damaged fuel
-  : Fuel pellet melted
-  : Void (fuel melted down)

- Melting starts from the central part of the core.
- In 16 hours after scram, most part of the core fell down to the RPV bottom.


Unit 1 RPV Failed Grossly and Units 2&3 Partially



Unit 1 Melt: 3/11~19:00 RPV Fails ~3/12 ~15:00
 Unit 2 Melt: 3/14 ~20:00
 Unit 3 Melt: 3/13 ~09:00


Unit 1 Core Melt to the Floor

Loss of Isolation Condenser Cooling: Early Core Melt & Significant Vessel Penetration & Core Drop




Unit 1 Corium Penetrated
~70cm (30%) of the 260cm
thick floor concrete
Above the 4cm steel liner
plate.

There is 7M of base mat
concrete below
the liner plate



Unit 2 & 3 Core Melt In Vessel



**Longer Core Cooling
With Turbine Driven
Pumps Resulted in Less
Aggressive Core Melting**

**Projected Vessel Breach
with some Melted core
on the floor**

**Minor Concrete
Penetration (if any) due
to low Melted Core Mass
and Flooded Drywell
Floor**

Core Cooling Established With Fire Truck Sea Water Injection




Bleed & Feed Core Cooling Established

Seawater Injection Started Using Fire Engine Pump

Shift to Fresh Water Injection: To Dissolve Possible Salt Cakes

Vapor Venting




Immediately After Unit 3 Explosion

3/14/11 ~10:00AM JST



Spent Fuel Pool in Reactor Building



Unit 4 Pool




Figure 20. Mark I General Electric, GE BWR Containment.


~350,000 Gal

U4:1331 Assemblies SF ~100 day old


U3:514 Assy SF~ 200 Days old

U2: 587 Assy SF ~120 Days Old

Unit 4 Reactor Building



Reuters



TEPCO

Unit 4 Spent Fuel Pool Water Sampling



**Boom Inserting Probe
~11-04-11**



**400ml Sample Probe
~11-04-11**



Unit 4 Spent Fuel Pool



Sampling Indicates Little If Any Fuel Damage
Low Cesium Levels in 90Bq/ml
Water Level Lowered For Seismic Safety


Units 2 & 3 Pools Have Some Damaged Fuel- Not Melted




- Cesium 137 Levels in 150,000 Bq/ml
- Low Iodine, indicative of older stored fuel
- High Ph ~11.3
- Al Rack Corrosion
- Adding Boric Acid

**Building Debris In Unit 3 Pool
~ R/Hr at U3 Refueling Floor**

Unit 4 Explosion: H2 From Unit 3




Dry Storage Cask Facility



Relative
Low Elevation

Storage Only Metal Cask



Main features

- **Cylindrical forged carbon-steel casks**
- **Similarity with transport casks**
- **5-115T 52 Assy Casks & 4-96T 37 Assy Casks**
- **Helium filled**
- **Steel for γ -ray shield/ resin for neutron shield**
- **Borated-aluminum alloy basket for sub-criticality**

Dry Storage Facility Was Flooded But All 9 Casks Intact



Fukushima Stabilized

- **Established Recirculation Core Cooling**
 - **Damaged Pressure Vessel(s) & Containments**
- **Mitigating Airborne Releases**
- **Mitigating Water Releases**
- **Gaining Building Access to Start Recovery Activities**
- **Managing Solid Wastes**
- **Maintain Personnel Safety: High Rad Areas**
- **Addressing Evacuation Zone Situation**

Units 1-4 After U4 Building Explosion 3/16



Units 3, 2, & 1 Looking Down



Units 4 & 3 Looking Down



Unit 4 Fuel Pool-Side



L. Barrett Consulting LLC

44


海島第一座核力發電廠 4 号機 (2 / 16 DM 攝影)

Unit 3 & Unit 4



Unit 3 Spent Fuel Pool

3/16



福島第一原子力発電所 3号機(3/16 PM撮影)

L. Barrett Consulting LLC

Water Spray to Unit 3 Pool Area




Unit 4 Reactor Building

Water Injection Boom To Spent Fuel Pool



Established Core Recirculation Cooling Once Water Processing Started: July



Need Water Recirculation System To Stop Feed & Bleed Venting & Radioactive Water Creation

~30+M gallons High Rad Water


Unit 4 Reactor Building Structural Integrity Seismic Risk Reduction



- Explosions Weaken RB Structure
- A Large Earthquake Aftershock May Cause Building Failure
- Structurally Strengthen Building



- Adding Steel & Concrete under Pool



Working Conditions are Challenging

Restoring Power In High Radiation & Contaminated Areas



U2 Reactor Building Conditions




Robots First



Personnel Second

Ground RB Floor



Water 4M deep in Basement

Site Airborne Dust Mitigation



Dust Fixation Resin Application



Dust Vacuum Filter/Collection Unit



Before




After

RB Airborne Mitigation Containment Canopy Concept Design-1



Fast Remote Construction Design Concept




**Unit 1 RB Filtered Enclosure
55M High & 47M X 42M**



Laser Image New Enclosure

Unit 1 Canopy Detailed Design-2



**Creative Remote
Construction Concepts**



Mockup Const Training

**Construction Sequence
Planning**

Unit 1 Canopy Construction-3



Foundation Clearing



Frame Assembly

Unit 1 Canopy Construction Step-4



Wall Panel Emplacement



Enclosure Completed: Oct

HVAC Fan/Filter/Monitor Equipment Installed

Contaminated Water Containment Overflow from U2 Reactor Bldg to Turbine Bldg to Intake Structure Wall Crack to Sea

27,000 Ci Cs-137 Released this Path 4/1-6

-Reference Chernobyl was 2M Ci Cs-137 released



**Non-Safety Grade
intake Structure**



**Radioactive Water
Leak 11-04-02**



**Leak Reduced 11-04-04
Leak Sealed 11-04-06
Sodium Silicate Injection**

Sealing Other Leakage Paths to Sea




Concreting One of ~37 Cable & Pipe Chase Paths

Water Retention Tank Farms

Underground Tanks Under Construction



Accident Water Management



Relative
Low Activity
Released

20-50 Million Gallons Of Highly Radioactive Water To Be Transferred To Onsite Tankage

Water Release Mitigation

Contain/Retard Intake Structure Cs/Sr Contamination



**Sluice Gate to Minimize Outflow
To Ocean**




Zeolite Bags To Adsorb Cs/Sr

Water Release Mitigation

Silt Fence to Retard Cs/Sr Release to Sea



Mitigate Basement Leakage Into Groundwater Paths To Sea



Planning Underground Barrier Walls to Bed Rock

Improved Contaminated Water Drainage Retention Wall




Figure of basic plan of shielding wall



US Fresh Water Barge On Site-April



Japanese ship hauling US Navy water barge




Japanese Tow Operators

Water Recirculation Processing Plan

Four Stage System

1. Oil Removal: Toshiba
2. Cesium Removal: Kurion
3. Fission Products Removal: AREVA
4. Salt Removal: Hitachi



* oil separators, radioactive material treatment instruments... Installed within the Process Main Building,

Cesium absorption Instruments... Installed within the Incineration Workshop Building

L. Barrett Consulting LLC

Oil Removal



Separator Unit



Separator Internals


Cesium Removal Stage



Individual Zeolite Beds



Shielded Skids



Salt Removal Stage



U4 Reverse Osmosis Unit




Evaporator Unit

Underground Tanks for High Activity Liquid Wastes



New Water Processing System

Simplified Active Water Retrieve and Recovery System (SARRY)



Toshiba Lead

2 Lines of 8 Larger (24Ton) Zeolite/Silicate Filter Beds to Augment Initial Kurion/AREVA System -200gpm capacity

September Operation

Wastes From Water Treatment

- **Water Treatment Systems Produce High Cs-Sr Wastes**
 - ~200 Kurion Zeolite Canisters (90cm dia X 2.3M high, 300M³)
 - ~580M³ of AREVA Precipitation Sludges
 - ~150 SARRY (1.4M dia x 3.5 M high) Zeolite Canisters
- **Onsite High Radiation Storage Area**

High Radiation Demineralizer Storage



744 Canister Storage Facility

**~330 Cans January 2012
1.4M Dia & ~3M high each
~1,000rRhr**


Reactor Defueling Plans

Cleanup-Defueling Process

Step wise Access Toward Core Internals



**Initial Building Cleanup
Robotic Equipment**




**Planned Steps Toward
Defueling Access with Robotic
Cranes- High Gamma Fields**




**Restore Building
Infrastructure, e.g. Crane
Capacity**

1. Gain Building Access Decon & Build Infrastructure




2. Remove UnDamaged Spent Fuel From Reactor Building Storage Pools Near Conventional Fuel Handling




**Unit 4 First Followed By Units 1-3 Pools
Start in 2 Years & Finish in 10 Years**


3. Find Containment Leakage Paths



5. Flood Containment & Work Upwards



6. Flood Further & Evaluate Internal Conditions




7. Preparing For Melted Core Removal

Secondary Containment Established


Remove Containment & Vessel Heads

Build Core Debris Canister Loading System




Finish in 10 Years

8. Remove Melted Core Debris From Reactor Vessel



Start in 10 Years

9. Remove Melted Core from Floor Drill/Burn Down Through Reactor Vessel



Complete in 20 to 25 Years

10. Store Core Debris For Final Disposition e.g. TMI Experience



Spent Fuel Can Transfer Cask



TMI Transport Cask



Dry Cask Storage



TMI Core Debris In Idaho

11. Decontaminate & Decommission Buildings



Example of TMI Decontamination Operations (Took ~10 Years)


Fukushima: Complete 30 to 40 Years (2040-2050)



Offsite Contamination Impacts

Annex 2

Results of airborne monitoring by MEXT and DOE
 (Total surface deposition of Cs-134 and Cs-137 inside 80 km zone of Fukushima Dai-ichi NPP)



-Multi Billion Dollar Government Sponsored Cleanup for Areas > 1uSv/hr above background (~>870mr/yr & 500mr/yr)

-Limits of 500Bq/kg foods

-Impacts large areas:
 ~1,800 Km² @ 5mSv/yr (500mr/yr)

~13,000Km²@1mSv/yr (100mr/yr)

-High Cost: \$3B +

Offsite Cs/Sr Contamination

Offsite Decontamination



House Roofs



Parking Lots



School Buildings



Children's Playgrounds

Decontamination Solid Waste Management



Temporary Storage of School Playground Dirt

Expecting 29 Million M3 LLW(9KM2 10M deep volume) of Offsite Contaminated Soil to be Managed


-State Owned Forests & Voluntary Storage Sites Planned

Difficult Siting Issues Ahead for Final Disposal Facilities For High Level Waste, Intermediate Wastes, and Low Level Wastes

Human Feelings & Reactions




Cleanup Standards Have Significant Resource Requirement Variations



Cleanup Level at 1 mSv/y:

- 13,000 km², or
- 3% of Japan's land mass, or
- About the size of Connecticut
- Costs at \$15.6 B



Government/Society Decisions

- **National Energy Policy & Implementation**
 - Balance Impacts, Risks, Benefits & Costs of Energy Supplies With Actions
- **Regulatory Policy & Organizational Structures**
- **Resource Allocation**
 - How Clean?
 - What Acceptable Impacts & Risks?
 - How Much?
 - When?
 - Where?
 - Who?

Personal Conclusions

- **Fukushima Was an Industrial Catastrophe Caused By an Unexpected Huge Tsunami**
- **Plant Staff Established Control Under Great Duress**
- **Public Health Impacts Are Very Low**
- **Societal Impacts and Costs are Very High**
- **Japan Faces Many Societal Challenges Ahead**
- **The US Cleaned Up, Learned, and Became Stronger After Three Mile Island**
- **Japan Can Also With Fukushima**

Lake H. Barrett

Lake@Lbarrett.com

Lake Barrett is a part time independent consultant in the energy field. He has worked in the nuclear energy and nuclear materials management areas for over 4 decades, most recently as the former head of the US Department of Energy's Office of Civilian Nuclear Waste Management which is responsible for implementing the United States' programs for spent nuclear fuel and high-level radioactive waste, as mandated by the Nuclear Waste Policy Act. In that capacity, he led the complex scientific Yucca Mountain Geologic Repository program through the statutory site selection process culminating with the Presidential site designation and following successful House and Senate votes.

He also served at U. S. Nuclear Regulatory Commission, where he was directly involved with the early response to the Three Mile Island reactor accident and became the Site Director, responsible for regulatory programs during the stabilization, recovery, and cleanup of the damaged reactor. He also has had extensive managerial and engineering experiences in DOE's Defence Programs and private industry at both Bechtel Power Corporation, with commercial nuclear power plants, and Electric Boat Division of General Dynamics with nuclear reactor and submarine systems design, operation, and decommissioning.

Backup Slides

Cold Shutdown Safety Plan

Countermeasures for protecting Core Damage

(1) Flooding Protection Countermeasures for sites and buildings

Installation of tidal embankment, board, and wall and flood protection of door and penetration

(2) High Pressure Cooling Water Injection Facilities (Required within 1-hour)

Concepts

-High pressure injection is initially required due to high reactor pressure in the case that the plant experiences an abnormal shutdown.

-During the accident, some motor-driven equipments were inoperable due to the station black out (SBO). Hence, a steam-driven high pressure facility is the key issue.

-Furthermore, when choosing motor-driven high pressure cooling water injection facilities, it is important to select equipment with minimum operating requirements.

		SBO	
RCIC	steam-driven	○	
SLC or CRD	motor-driven		×
HPCS			

(3) Depressurizing Equipment (Within 4-8 hours)

Concepts

-Depressurization of the reactor pressure vessel is essential in order to remove heat and bring it to a cooling stage.

-During the Fukushima accident, the DC power necessary to operate the main steam safety relief valve for depressurizing was insufficient. In addition to securing N2 for valve operations, securing a power source is necessary.

(4) Low Pressure Water Injection Facilities (Within 4-8 hours)

Concepts

-Low pressure cooling water injection equipment consists of an emergency system, a make-up water condensate system (MUWC) and a fire protection system. In the case of the SBO, only the diesel-driven fire pumps (DDFP) of the FP will be operable.

-Preparing reliable low pressure injection equipment is important including the fire-engine use.

		SBO	
DDFP	diesel-driven	○	
MUWC	motor-driven		×

(5) Heat Removal/Cooling Facilities

1) PCV venting (Within 1-2 days)

Concepts

-In the case that seawater cannot be used as a cooling source, suppression chamber venting that utilizes air as a cooling source is necessary.

-In order to conduct suppression chamber venting, opening motor-operated (MO) valves as well as air-operated (AO) valves are necessary.

2) Heat removal via Shutdown Cooling Mode (Within 3-7 days)

Concepts

-Shutdown cooling mode procedures by residual heat removal system (RHR) that utilizes sea water as a cooling source is necessary.

-Thus, in addition to ensuring a power source, restoring the seawater system utilized as the ultimate heat sink for preparing alternative pumps, or motor repairs is necessary.

Reactor Core Isolation Cooling System (RCIC)

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
Pump/Turbine	Flood protection for the RCIC Room	Establishing manual activation procedures
DC Power Supply (Battery, switchgears, etc.)	Flood protection for the battery room and the area where the main bus panel is located (or considering rearrangement)	Preparing Power-Supply cars

Stand by Liquid Control System (SLC) or Control Rod Drive (CRD)

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
SLC pump or CRD pump	-	Flooding protection for the pump area
Water Source	-	Establishing water supply procedure from the purified water tank
AC Power	-	Flooding protection for power supply equipment, including Emergency Diesel (EDG), deploying power-supply car, securing an outside power source as an alternative to the EDG.

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
N2 tanks	-	Preparing spare tanks
DC power supply (Battery, switchgears, etc.)	Flood protection for the battery room and the area where the main bus panel is located (or considering rearrangement)	Preparing portable batteries

Fire Protection System (FP)

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
Diesel-driven fire pumps	Flood protection for the pump room	Preparing fire engines and constructing water transfer lines, and establishing procedure for seawater injection
Batteries	Flood protection for the battery room	Preparing portable batteries
Diesel fuel	Fuel deployment (including delivery logistics)	-

Make-up Water Condensate system (MUWC)

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
MUWC pump	Flood protection for the pump room	Establishing procedures for supplying of water among tanks
AC power	Flood protection for power supply equipment, including EDG or considering rearrangement	Preparing power-supply cars, securing an outside power source as an alternative to the EDG

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
AC power (MO-valve, solenoid valve for AO-valve)	Flood protection for power supply equipment including EDG or considering rearrangement	Preparing power-supply cars, portable AC generator or portable batteries
Compressed air (For AO-valve operation)	Portable air compressor (or tank preparation)	Remodeling AO-valve so that it can be operated manually

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
AC power (RHR pump)	Flood protection for power supply equipment including EDG or considering rearrangement	-Preparing alternative pump -Preparing mobile heat exchangers
RCW/RSW pump	Preparing spare motor	-
AC power (RCW/RSW)	Flood protection for power room	Preparing Power-Supply cars, maintaining an outside power source as an alternative to the EDG.

3) Heat removal from spent fuel pool (Within 7-10 days: Depending on decay heat from spent fuels)

Concepts

-Spent fuel pool cooling and cleanup system (FPC) is basically tsunami-resistant since it is located inside the reactor building. Hence it is important to maintain the power source.

-Furthermore, in light of having a sufficient amount of time to respond, monitoring utilizing the instruments is important.

(6) Ensuring power supply to the monitoring instruments (Required within 1 hour)

Concepts

-During the Fukushima accident, the monitoring instruments were rendered inoperable and restoring power to the instruments took time.

-Thus ensuring immediate power supply for instruments is important.

(7) Mitigation measures following reactor core damage

Concepts

-During the accident, not only was the containment function lost, but also restoration efforts were seriously hampered due to the hydrogen explosion caused by the possible leak of hydrogen from the primary containment vessel to the building.

-In light of defense in depth, it is important to establish countermeasures in the case of the reactor core damage, which happened at Fukushima Daiichi

(8) Common Countermeasures

-In addition to implementing each countermeasure, it is important to reinforce the supporting work and auxiliary equipment for safe and efficient activity in order to achieve the aforementioned countermeasures effectively.

Other mid and long-term Technical Issues

-In this study, the aforementioned core damage countermeasures have been established. In addition, mid and long-term technical issues such as those listed in the right-hand table should be considered

-These technical issues will be considered separately.

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
FPC pump	Flooding protection for the pump room ----- Installation of water level detection instruments or a thermometer inside the pool	-Preparing fire engines -To establish redundancy with fire protection piping
AC power	Flooding protection for power supply equipment or considering rearrangement	Preparing Power-Supply cars

Necessary Equipment	Flooding Countermeasure for system	Countermeasure in a flexible manner
DC power	Waterproofing the battery room and the area where the main bus panel is located (or considering rearrangement)	-Preparing portable batteries -Preparing Power-Supply cars and portable battery chargers

Items	Countermeasure
Hydrogen Accumulation Prevention	Installing equipment or establishing procedures for drilling holes through the roof or opening the blow-out panels in order to improve reactor building ventilation.
Mitigation of Radioactive Material release	Establishing the water injection procedures to the PCV via fire engines etc. as is being done with the suppression chamber venting. (Established for smooth venting via water filtering)

Items	Countermeasure
Outside Power Source	Reviewing the seismic improvement for the substation facilities, assessing the destruction of the embankment that could lead to transmission tower damage, and setting up facilities that will contribute to power transmission reliability.
Debris Removal Equipment	Preparing equipment to remove debris hampering restoration activity.
Securing communication tools	Establishing flexible communication measure such as the preparation of walkie-talkies or satellite phones as well as ensuring a power source
Securing Lighting Equipment	Preparing high power lighting equipment and headlights that will allow workers free use of both hands so that they will be ready to respond safely, quickly and precisely.
Health Protection Equipment	An abundant supply of protective gear, masks, AFDs, portable air refreshers, etc. should be on hand along with the deployment of the power supply car in order to ensure that workers will be able to restore the main control room ventilation system promptly.


Items	Action Plan
Isolation Signal Review	During the Fukushima accident, the loss of the isolation condenser cooling function was caused by the valve closing up due to loss of DC power. Hence, the concept concerning the isolation signal should be reviewed.
Venting line improvement	In order to improve venting that is able to significantly filter out radioactive materials, measures such as the aggressive activation of the Rupture Disk will be looked into while taking the accidental release of radioactive materials into consideration.
Mitigation measures for radioactive material release during venting	The design of a filter vent to mitigate the release of radioactive materials will be considered.
Surveillance Instrument Improvements	Given that the water level gauge measurements deviated greatly from the actual value at the power station, research and development in this area will be developed.

Defueling Plan

Attachment

Main Schedule of Mid-and-long Term Roadmap towards the Decommissioning of Fukushima Daiichi Nuclear Power Station Units 1-4, TEPCO

(Provisional translation)



*This roadmap will be updated in consideration of the on-site situation and the latest research and development results.